



INVITATION FOR BID 2021-06

ANIMAL SHELTER NEW CONSTRUCTION

Issue Date

October 14, 2021

Bids Due – (Bid Opening)

BIDS DUE NO LATER THAN 5:00 P.M.

ON OCTOBER 21, 2021

October 21, 2021

@6:30 p.m.

**@ Regular City Council
Meeting**

To

Diana Franco, City Secretary

432-586-3460 Voice

432-586-2220 Fax

city.sec@cityofkermit.net

RFP 2021-06

The City of Kermit is requesting proposals for New Construction at Animal Shelter. A copy of such Specifications may be picked up at Kermit City Hall, 110 S. Tornillo Kermit, TX between Monday – Friday from 8am-12noon and 1pm and 5pm. You may also visit our website at www.kermittx.us

Sealed Bids, signed and in the original only, subject to the Invitation for Bids, Provisions and Specifications will be received at the Kermit City Hall, Kermit, Texas until 5:00 p.m. Central Standard Time on October 21, 2021.

All proposals must be sealed and marked

“RFP 2021-06 NEW CONSTRUCTION - ANIMAL SHELTER

And shall be delivered or mailed to:

City of Kermit
110 S. Tornillo
Kermit, TX 79745
ATTN: Diana Franco

Animal Shelter Phase 1

Metal Building

Weld up a 20'x20'x10' Metal Building 2:12 Pitch
with 2-6'x20' roof awnings 1:12 Pitch
Awnings will have concrete slab
Awnings 20'x40' kennel area will be closed off with
fence panels

Building Plan:

20'x20' in door dog kennel area
6'x20' out door kennel area on each side of
building

Building-400 sq.ft

Awnings-240 sq.ft

Total: 600 sq.ft.

Package Includes:

5 1/2" concrete slab at 3500 psi with fiber and 3/8"
rebar at 20" squares

20'x20' building area and all kennel partition walls
will be 8"x16" cinder block 36" tall

Cinder block will be concrete filled in 3' increments
for strength to support metal building

Metal Building will be built on top of cinder block
stem wall

2-Total - 6"x4"x5' floor gutters with floor drains
inside kennel area

1 Beam steel rafters

6" Cee Purlin

26 gauge class 4 metal R-Panel

Reinforced insulation

Gutter and downspouts

Full trim out around all openings

2-36" steel entry door

Dog Kennel: Install galvanized steel chain link
fence panels.

16- Chain link gates

Kennels will be closed off to ceiling from cinder block stem walls inside and out with chain link fencing

Standard electrical Includes:

200 amp service breaker panel

3- Led lighting inside building

4- 120v plugs

1- 220 Volt junction box for hvac system

Hvac- 1-1 1/2 ton dual head mini split

Plumbing Includes:

4" pvc drain line for floor gutters

3- water faucets, 1-Interior of building, 2-Exterior of building

All plumbing & electrical will be stubbed out of building

Plumbing tie in I.E fresh water & septic lines not included in bid

Ditching if any required for plumbing \$27 ft.

includes all pipe and fittings required for proper tie

Does not include new water or sewer taps if required

New electrical service if required will result in additional charges

New service cost \$3,700 Includes: Pole, meter base, discount, weather head

Any ditching required for electrical will be \$30 foot

includes all wire and conduit

Up to 200 linear feet

Dirt Work: Dirt work if any for slab build up not included

Bid Offering: \$ _____

Written Bid Amount: _____

BIDDER INFORMATION BELOW:

Bidder's Name: _____

Address: _____

Telephone Number: _____

Cell Number: _____

Signature: _____

Date: _____

Comments: _____

